BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of the Work : Providing Cement Pipe 1mtr Dia to Ganesh Layout Park in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	50	1056 - Hire Charges of Hydralic Excavator 1 Cum bucket including Operator and Fuel etc complete as per specifications and directions of engineer in charge of the work	Hrs	1008.00	
2	92.00	KSRRB M2900-2.1: Laying reinforced cement concrete pipe NP4 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications, A.1000 mm dia,etc complete as per specifications and directions of engineer in charge of the work	M	10022.40	
3	4	1087 - Hire Charges of Crane charges including Operator and Fuel etc complete as per specifications and directions of engineer in charge of the work	Day	3200.00	
4	1.60	Providing and laying in position **plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs** using **40mm** and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, **in foundation and plinth**, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4290.84	
5	1.60	Providing and laying in position plain cement concrete of **mix M15 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4779.00	

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ಸಿದ್ದಪಡಿ ಮಾಡಿದಂತೆ/
ಸಿದ್ದಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ಸಿದ್ದಪಡಿಗಳ ಸಂಖ್ಯೆ .....Nil.....

31/10/2013

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92